

Model HCBMS

MACHINE SPECIFICATIONS

Auxiliary Engine:

STANDARD

MAKE: John Deere

MODEL: 4045T, Balanced diesel engine

RATED H.P.: 100 RATED R.P.M.: 2,500

MAXIMUM TORQUE: 274 ft./lb.

OPTIONAL

Highway will work with the following:

• Caterpillar

- Cummins
- Detroit
- Deutz
- Ford
- Perkins

Consult factory for models available.

Transmission:

Four (4) speeds forward and one reverse 11¾" torque converter Torque converter oil cooler

Fuel Source:

STANDARD

Fuel supplied by chassis fuel tank (diesel/diesel)

OPTIONAL

50 Gallon fuel tank with mechanical gauge

Torque & R.P.M.:

STANDARD

1s 21,000 ft./lbs. @ 19.8 RPM

2nd 10,000 ft./lbs. @ 41 RPM

3rd 5,300 ft./lbs. @ 75 RPM

4th 3,600 ft./lbs. @ 126 RPM

Kelly Bar:

2¾" X 3½6" rack bar 4140 tool steel, heat treated ½" auger pin hole

Auger Capacity:

56" Intermittent 24" Continuous

Hole Depths:

STANDARD

101

OPTIONAL

Up to 421

Final Drive:

Special design pinion with a 16" ring gear Steel carrier with replaceable thrust plates

Hydraulic System:

17 G.P.M. gear pump 2,100 P.S.I. main system pressure 20 gallon oil reservoir In line return filter

Boom Leveling:

STANDARD

20 DEGREES LEFT

45 DEGREES RIGHT

15 DEGREES OVER VERTICAL

Options available, consult factory for special applications.

Cab Guard:

OPTIONAL

4""C" Channel with expanded metal top and tread plate bottom

Options available, consult factory for special applications.

Turntable Base:

STANDARD

95" diameter, 4" ship & car channel rolled ring

240 degree rotation

120 series chain run through hydraulic speed reducer

OPTIONAL

#1, 35 Degree Pivot base, 100" travel with 36" slide.

#2. Fixed base.

Outriggers:

STANDARD

Rear "A" frame

OPTIONAL

Straight down jacks Two sets of "A" Frame outriggers Spring lockouts

Pivot Base:

Constructed of 6" wide flange I-beam 25 lbs./ft. Full length greasable main frame guides

Main Frame:

Constructed of 6" wide flange I-beam 25 lbs./ft. 36 inches of In/Out slide travel

Mast:

5" O.D. tubing to house rack bar

Derrick:

7½" O.D. tubing construction Telescoping and non-telescoping

Telescoping Derrick:

OPTIONAL

9' Telescoping derrick

Pole Guides:

OPTIONAL

- #1. Mechanical linkage fixed pole guides with side rollers
- #2. Mechanical linkage tilting pole guides with side rollers

Winch:

OPTIONAL

Planetary winch 10,000 lb. On first wrap. 125' of 7/16" wire rope

Tool Circuit:

OPTIONAL

- #1. Fixed position tool circuit with control valve.
- #2. Tool circuit with hose reel 25 hydraulic hose.

Water Tank:

OPTIONAL

- #1. 100 Gallon steel, poly or aluminum.
- #2. 200 Gallon steel, poly or aluminum.

Auger Storage:

OPTIONAL

- #1. Auger drop box, located curb side.
- #2. Auger stakes. (location to be determined)

Tunnel Storage:

OPTIONAL

Enclosed tunnel storage with lockable rear door Fabricated from sheet or expanded metal

Digger Weight:

Base weight digger only 11,500 lbs. (approx.)

Chassis or Carrier:

84" Cab to Axle minimum 26,000 GVW Single axle minimum

Other Options:

Paint colors, Tool boxes, Trailer hitches, Panel lights, Work lights, Safety lighting, Grounding systems, Auger adapters & extension, Augers, Tooling, Hydraulic tools, Outrigger pads, Wheel chocks, Front winches.

NOTE: all dig depths are based on a 36" chassis frame height and 36" long auger.

HIGHWAY MANUFACTURING

133 Cad Street N.E., Hopkins, MN 55343 Prione (612) 938-2889 Fax (612) 938-0159

Weijisting www.abur-bighway.com